

SWIMMING POOL - WATER ANALYSIS REPORT

Client Name: TAFAWUQ FACILITY MANAGEMENT, ABU DHABI			
Site Name:	AL NOOR TOWER	Visit Date:	04-08-2020
Source of Sample	Swimming Pool	Sample Point	Main Swimming Pool

TEST RESULT

No	Parameter	Control limits	Test Results
1	pH at 25°C	7.2 - 7.6	7.51
2	Conductivity at 25°C, µs/cm	---	384
3	TDS, ppm	Max 1500	249
4	Alkalinity	80 - 120	91
5	Calcium Hardness	200 - 500	188
6	Residual Chlorine	1.0 - 3.0	1.05
7	Cyanuric Acid	20 - 60	24
8	Dip slide	<10 ³	ND

*** All test results expressed in parts per million (ppm) as CaCO₃ except pH and conductivity (µmhos).

COMMENTS AND RECOMMENDATIONS

- All Parameters are within control limit – No action Recommended.

Reported By,

P. M. Nagaraj
Service Engineer

