

TEST REPORT

Report No: QMTL/R-148341/2021

CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES Abu Dhabi PO Box : 131463 United Arab Emirates		Sample ID	QMTL/S-148341
		Date Received	14 Feb 2021
		Date(s) Tested	14 Feb 2021 - 16 Feb 2021
ATTN : MR. JASMAN PINTO		Date Reported	28 Feb 2021
Sample Description	Hot Calorifier, Plant Room -1		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital, Abu Dhabi	Sampling Date/Time	14.02.2021 / 4:25 PM
Sample Container	1x500ml PB	Sampling Point	Valve
Sample Receipt Temp	4°C	Sample Onsite Temp	26.9°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
MICROBIOLOGICAL PARAMETERS				
Total Bacterial Count*	APHA 9215 B -23rd Edition	CFU/ml	500	48
Total Coliforms*	APHA 9222 B -23rd Edition	CFU/100 ml	-	Zero
Fecal Coliforms*	APHA 9222 D -23rd Edition	CFU/100 ml	-	Zero
Pseudomonas aeruginosa*	APHA 9213 E -23rd Edition	CFU/100 ml	-	Zero
E.coli*	APHA 9222 I -23rd Edition	CFU/100 ml	-	Zero

The Analysis results denoted by (*) are part of the laboratory ENAS Accreditation to ISO/IEC 17025 : 2017.

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, NP: Not Provided, NA: Not Applicable, WI: Work Instruction
Test method deviation	None
Test performed by Emp#	103 & 14
Report prepared by Emp#	72
The above test results are only applicable to the sample(s) referred above.	

Reported By
ANILA GEORGE
LABORATORY MANAGER

This report is system generated, signature, stamp/ seal are not required.

The test report shall not be reproduced (except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

END OF REPORT

TEST REPORT

Report No: QMTL/R-148342/2021

CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES Abu Dhabi PO Box : 131463 United Arab Emirates		Sample ID	QMTL/S-148342
		Date Received	14 Feb 2021
		Date(s) Tested	14 Feb 2021 - 16 Feb 2021
ATTN : MR. JASMAN PINTO		Date Reported	28 Feb 2021
Sample Description	Hot Calorifier, Plant Room -2		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital, Abu Dhabi	Sampling Date/Time	14.02.2021 / 4:30 PM
Sample Container	1x500ml PB	Sampling Point	Valve
Sample Receipt Temp	4°C	Sample Onsite Temp	26.1°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
MICROBIOLOGICAL PARAMETERS				
Total Bacterial Count*	APHA 9215 B -23rd Edition	CFU/ml	500	40
Total Coliforms*	APHA 9222 B -23rd Edition	CFU/100 ml	-	Zero
Fecal Coliforms*	APHA 9222 D -23rd Edition	CFU/100 ml	-	Zero
Pseudomonas aeruginosa*	APHA 9213 E -23rd Edition	CFU/100 ml	-	Zero
E.coli*	APHA 9222 I -23rd Edition	CFU/100 ml	-	Zero

The Analysis results denoted by (*) are part of the laboratory ENAS Accreditation to ISO/IEC 17025 : 2017.

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, NP: Not Provided, NA: Not Applicable, WI: Work Instruction
Test method deviation	None
Test performed by Emp#	103 & 14
Report prepared by Emp#	72
The above test results are only applicable to the sample(s) referred above.	

Reported By
ANILA GEORGE
LABORATORY MANAGER

This report is system generated, signature, stamp/ seal are not required.

The test report shall not be reproduced (except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

END OF REPORT

TEST REPORT

Report No: QMTL/R-148343/2021

CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES Abu Dhabi PO Box : 131463 United Arab Emirates		Sample ID	QMTL/S-148343
ATTN : MR. JASMAN PINTO		Date Received	14 Feb 2021
		Date(s) Tested	14 Feb 2021 - 16 Feb 2021
		Date Reported	28 Feb 2021
Sample Description	Hot Calorifier, Plant Room -3		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital, Abu Dhabi	Sampling Date/Time	14.02.2021 / 4:35 PM
Sample Container	1x500ml PB	Sampling Point	Valve
Sample Receipt Temp	4°C	Sample Onsite Temp	26.4°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
MICROBIOLOGICAL PARAMETERS				
Total Bacterial Count*	APHA 9215 B -23rd Edition	CFU/ml	500	32
Total Coliforms*	APHA 9222 B -23rd Edition	CFU/100 ml	-	Zero
Fecal Coliforms*	APHA 9222 D -23rd Edition	CFU/100 ml	-	Zero
Pseudomonas aeruginosa*	APHA 9213 E -23rd Edition	CFU/100 ml	-	Zero
E.coli*	APHA 9222 I -23rd Edition	CFU/100 ml	-	Zero

The Analysis results denoted by (*) are part of the laboratory ENAS Accreditation to ISO/IEC 17025 : 2017.

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, NP: Not Provided, NA: Not Applicable, WI: Work Instruction
Test method deviation	None
Test performed by Emp#	103 & 14
Report prepared by Emp#	72
The above test results are only applicable to the sample(s) referred above.	

Reported By
ANILA GEORGE
LABORATORY MANAGER

This report is system generated, signature, stamp/ seal are not required.

The test report shall not be reproduced (except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

END OF REPORT