



Microbiology Test Report

Customer Details

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.

Report No. WA-R-L-2007-14526



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14042

Sampling Date	: 15/07/2020	Report Date.	: 19/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 18/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Kitchen Tap
Sampling Point	: Kitchen Inside	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Escherichia Coli	APHA 9222 B,H& I 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Faecal Coliforms	APHA 9222 D 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Heterotrophic plate count	APHA 9215 B 23rd Ed. 2017	CFU/ml	Not Detected	100CFU/ml
Pseudomonas aeruginosa	CCFRA 2.5.2 5th Ed. 2007	CFU/250ml	Not Detected	Zero
Total Coliforms	APHA 9222 B 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml

Note : Not Detected= \leq 1CFU

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested results of the sample are found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; APHA-American Public Health Association; CCFRA-Campden Chorleywood Food Research Association.

Signed for and on behalf of Wimpey Laboratories



Dr. Suresh Murugan Ph.D

Senior Microbiologist

Test results relate only to the samples tested.This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-01 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Microbiology Test Report

Customer Details

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.

Report No. WA-R-L-2007-14524



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14041

Sampling Date	: 15/07/2020	Report Date.	: 19/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 18/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Washroom Tap
Sampling Point	: Near Cafeteria	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Escherichia Coli	APHA 9222 B,H& I 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Faecal Coliforms	APHA 9222 D 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Heterotrophic plate count	APHA 9215 B 23rd Ed. 2017	CFU/ml	Not Detected	100CFU/ml
Pseudomonas aeruginosa	CCFRA 2.5.2 5th Ed. 2007	CFU/250ml	Not Detected	Zero
Total Coliforms	APHA 9222 B 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml

Note : Not Detected=<1CFU

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested results of the sample are found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; APHA-American Public Health Association; CCFRA-Campden Chorleywood Food Research Association.

Signed for and on behalf of Wimpey Laboratories



Dr. Suresh Murugan Ph.D

Senior Microbiologist

Test results relate only to the samples tested. This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-01 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Microbiology Test Report

Customer Details

Report No. WA-R-L-2007-14520

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14039

Sampling Date	: 15/07/2020	Report Date.	: 19/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 18/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Main Tank
Sampling Point	: Near Kitchen Side	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Escherichia Coli	APHA 9222 B,H& I 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Faecal Coliforms	APHA 9222 D 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml
Heterotrophic plate count	APHA 9215 B 23rd Ed. 2017	CFU/ml	Not Detected	100CFU/ml
Pseudomonas aeruginosa	CCFRA 2.5.2 5th Ed. 2007	CFU/250ml	Not Detected	Zero
Total Coliforms	APHA 9222 B 23rd Ed. 2017	CFU/100ml	Not Detected	Zero/100ml

Note : Not Detected= \leq 1CFU

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested results of the sample are found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; APHA-American Public Health Association; CCFRA-Campden Chorleywood Food Research Association.

Signed for and on behalf of Wimpey Laboratories

Dr. Suresh Murugan Ph.D

Senior Microbiologist



Test results relate only to the samples tested. This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-01 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Legionella Test Report

Customer Details

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.

Report No. WA-R-L-2007-14525



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14042

Sampling Date	: 15/07/2020	Report Date.	: 26/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 25/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Kitchen Tap
Sampling Point	: Kitchen Inside	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Legionella	ISO 11731: 2017	CFU/L	Not Detected	Zero/L

Note : Limit of Detection=<1CFU/L

Procedure: WSOP-MB-0051 Direct Placing of Membrane on BCYE+L-Cysteine/Membrane Filter Followed by Washing Procedure in Funnel.

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested result of the sample is found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; BS-British Standard; ISO-International Organization for Standardization.

Signed for and on behalf of Wimpey Laboratories



Dr. Suresh Murugan Ph.D

Senior Microbiologist

Test results relate only to the samples tested. This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-03 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Legionella Test Report

Report No. WA-R-L-2007-14523

Customer Details

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14041

Sampling Date	: 15/07/2020	Report Date.	: 26/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 25/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Washroom Tap
Sampling Point	: Near Cafeteria	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Legionella	ISO 11731: 2017	CFU/L	Not Detected	Zero/L

Note : Limit of Detection=<1CFU/L

Procedure: WSOP-MB-0051 Direct Placing of Membrane on BCYE+L-Cysteine/Membrane Filter Followed by Washing Procedure in Funnel.

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested result of the sample is found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; BS-British Standard; ISO-International Organization for Standardization.

Signed for and on behalf of Wimpey Laboratories

Dr. Suresh Murugan Ph.D

Senior Microbiologist



Test results relate only to the samples tested. This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-03 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Legionella Test Report

Customer Details

Report No. WA-R-L-2007-14521

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14040

Sampling Date	: 15/07/2020	Report Date.	: 26/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 25/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Cooler Tap
Sampling Point	: Near Washroom Side	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Legionella	ISO 11731: 2017	CFU/L	Not Detected	Zero/L

Note : Limit of Detection=<1CFU/L

Procedure: WSOP-MB-0051 Direct Placing of Membrane on BCYE+L-Cysteine/Membrane Filter Followed by Washing Procedure in Funnel.

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested result of the sample is found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; BS-British Standard; ISO-International Organization for Standardization.

Signed for and on behalf of Wimpey Laboratories



Dr. Suresh Murugan Ph.D

Senior Microbiologist

Test results relate only to the samples tested.This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-03 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -



Legionella Test Report

Customer Details

Report No. WA-R-L-2007-14519

Crystalline Cleaning & Environmental Services

P.O.Box: 131463 Warehouse no: 84, M-45. Mussafah, Abu Dhabi, UAE.



Request No. : WA-Q-L-2007-02153

Sample No. : WA-S-L-2007-14039

Sampling Date	: 15/07/2020	Report Date.	: 26/07/2020
Analysis Start Date.	: 15/07/2020	Analysis End Date.	: 25/07/2020
Sample Location.	: Mountain Gate Property Investment	Sampled By	: Client Representative
Sample Identification	: Not Applicable	Sample Submitted as	: Water
Sample Certificate No	: Not Applicable	Sampling Method	: Not Applicable
Temperature °C	: Not Applicable	Site Observation	: Not Applicable
Sampling Container	: Plastic Bottle	Source of Sample	: Main Tank
Sampling Point	: Near Kitchen Side	Preservation	: Not Applicable
Sample Description	: Water		

Parameters	Test Methods	Units	Results	Specification
Legionella	ISO 11731: 2017	CFU/L	Not Detected	Zero/L

Note : Limit of Detection=<1CFU/L

Procedure: WSOP-MB-0051 Direct Placing of Membrane on BCYE+L-Cysteine/Membrane Filter Followed by Washing Procedure in Funnel.

Limits based on RSB Water Quality Regulation 2014. Schedule 1. Table F For Microbiological Parameters.

Remarks :The tested result of the sample is found to be satisfactory within the specified limits.

Analyst	Reviewed By	Method Variation
HS	SM	None

Key Words :CFU-Colony Forming Unit; BS-British Standard; ISO-International Organization for Standardization.

Signed for and on behalf of Wimpey Laboratories

Dr. Suresh Murugan Ph.D

Senior Microbiologist



Test results relate only to the samples tested. This report shall not be reproduced except in full, without the written approval of the Laboratory. This is a LIMS software generated document with E Signature.

Form No: WARF-MB-03 Issue No.:01 Rev No:00 Issued Date:22-01-2020

- End of Text -

POTABLE WATER ANALYSIS REPORT

Client Name: Mountain Gate Property Investment LLC.			
Site location	Mountain Gate Labour Camp	Service Visit:	15-07-2020
Sampled By	Crystalline Rep	Sample Location	RCC WATER TANK
Sample Type	Potable Water		


TEST RESULT

Physical Parameters			
	Parameter	Control Limits	Test Results
1	pH at 25°C	7.0 - 9.2	8.69
2	Conductivity at 25°C, µs/cm	----	199
3	Total Dissolved Solids (TDS)	Max 1000	129
4	Odor	Unobjectionable	ND
5	Turbidity (including suspended solids)	4.0	<1.0
6	Residual Chlorine	0.2 – 0.5	0.32
7	Calcium Hardness at 25°C	200	59
8	Total Hardness at 25°C	300	64
Inorganic Chemical Parameters			
1	Sulphate	Max 250.0	<10
2	Chlorides	Max 250.0	41
3	Iron	Max 0.2	<0.05
4	Copper	Max 1.0	<0.05
5	Zinc	Max 5.0	<0.05
6	Nitrate	Max 50.0	<1.0
7	Nitrite	Max 3.0	<0.05
8	potassium	Max 12.0	<5.0
9	Aluminium	Max 0.2	<0.05

*** All test results expressed in parts per million (ppm) as CaCO₃ except pH and conductivity (µmhos).

COMMENTS AND RECOMMENDATIONS

1	PH, Conductivity & TDS levels are normal
2	Residual chlorine levels are normal
3	Calcium hardness and Total Hardness levels are satisfactory
4	All inorganic parameters are within the control limit

Reported By,

Murugaraaj
Service Engineer



POTABLE WATER ANALYSIS REPORT

Client Name: Mountain Gate Property Investment LLC.

Site location	Mountain Gate Labour Camp	Service Visit:	15-07-2020
Sampled By	Crystalline Rep	Sample Location	Water Cooler
Sample Type	Potable Water		

TEST RESULT

Physical Parameters

	Parameter	Control Limits	Test Results
1	pH at 25°C	7.0 - 9.2	8.65
2	Conductivity at 25°C, µs/cm	----	187
3	Total Dissolved Solids (TDS)	Max 1000	121
4	Odor	Unobjectionable	ND
5	Turbidity (including suspended solids)	4.0	<1.0
6	Residual Chlorine	0.2 - 0.5	0.21
7	Calcium Hardness at 25°C	200	36
8	Total Hardness at 25°C	300	42

Inorganic Chemical Parameters

1	Sulphate	Max 250.0	<10
2	Chlorides	Max 250.0	29
3	Iron	Max 0.2	<0.05
4	Copper	Max 1.0	<0.05
5	Zinc	Max 5.0	<0.05
6	Nitrate	Max 50.0	<1.0
7	Nitrite	Max 3.0	<0.05
8	Potassium	Max 12.0	<5.0
9	Aluminium	Max 0.2	<0.05

*** All test results expressed in parts per million (ppm) as CaCO₃ except pH and conductivity (µmhos).

COMMENTS AND RECOMMENDATIONS

1	PH, Conductivity & TDS levels are normal
2	Residual chlorine level is satisfactory
3	Calcium hardness and Total Hardness levels are satisfactory
4	All inorganic parameters are within the control limit

Reported By,

P. Murugaraaj
Murugaraaj
Service Engineer



POTABLE WATER ANALYSIS REPORT

Client Name: Mountain Gate Property Investment LLC.			
Site location	Mountain Gate Labour Camp	Service Visit:	15-07-2020
Sampled By	Crystalline Rep	Sample Location	Kitchen Cooking Area
Sample Type	Potable Water		

TEST RESULT

	Parameter	Control Limits	Test Results
1	pH at 25°C	7.0 - 9.2	8.71
2	Conductivity at 25°C, $\mu\text{s}/\text{cm}$	----	206
3	Total Dissolved Solids (TDS)	Max 1000	134
4	Odor	Unobjectionable	ND
5	Turbidity (including suspended solids)	4.0	<1.0
6	Residual Chlorine	0.2 - 0.5	0.26
7	Calcium Hardness at 25°C	200	54
8	Total Hardness at 25°C	300	59


Inorganic Chemical Parameters

1	Sulphate	Max 250.0	<10
2	Chlorides	Max 250.0	43
3	Iron	Max 0.2	<0.05
4	Copper	Max 1.0	<0.05
5	Zinc	Max 5.0	<0.05
6	Nitrate	Max 50.0	<1.0
7	Nitrite	Max 3.0	<0.05
8	Potassium	Max 12.0	<5.0
9	Aluminium	Max 0.2	<0.05

*** All test results expressed in parts per million (ppm) as CaCO_3 except pH and conductivity (μmhos).

COMMENTS AND RECOMMENDATIONS

1	PH, Conductivity & TDS levels are normal.
2	Residual chlorine level is satisfactory
3	Calcium hardness and Total Hardness levels are satisfactory
4	All inorganic parameters are within the control limit

Reported By,

 Murugaraaj
 Service Engineer



POTABLE WATER ANALYSIS REPORT


Client Name: Mountain Gate Property Investment LLC.			
Site location	Mountain Gate Labour Camp	Service Visit:	15-07-2020
Sampled By	Crystalline Rep	Sample Location	Wash Room
Sample Type	Potable Water		

TEST RESULT			
	Parameter	Control Limits	Test Results
1	pH at 25°C	7.0 - 9.2	8.62
2	Conductivity at 25°C, µs/cm	----	175
3	Total Dissolved Solids (TDS)	Max 1000	114
4	Odor	Unobjectionable	ND
5	Turbidity (including suspended solids)	4.0	<1.0
6	Residual Chlorine	0.2 – 0.5	0.29
7	Calcium Hardness at 25°C	200	48
8	Total Hardness at 25°C	300	56

Inorganic Chemical Parameters			
	Parameter	Control Limits	Test Results
1	Sulphate	Max 250.0	<10
2	Chlorides	Max 250.0	43
3	Iron	Max 0.2	<0.05
4	Copper	Max 1.0	<0.05
5	Zinc	Max 5.0	<0.05
6	Nitrate	Max 50.0	<1.0
7	Nitrite	Max 3.0	<0.05
8	Potassium	Max 12.0	<5.0
9	Aluminium	Max 0.2	<0.05

*** All test results expressed in parts per million (ppm) as CaCO₃ except pH and conductivity (µmhos).

COMMENTS AND RECOMMENDATIONS	
1	PH, Conductivity & TDS levels are normal.
2	Residual chlorine level is satisfactory
3	Calcium hardness and Total Hardness levels are satisfactory
4	All inorganic parameters are within the control limit

Reported By,

 P. Murugaraaj
 Service Engineer

