

## TEST REPORT

Report No: QMTL/R-102688/2020

<b>CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES</b> Abu Dhabi PO Box : 131463 United Arab Emirates		Sample ID	QMTL/S-102688
		Date Received	07 May 2020
		Date(s) Tested	07 May 2020 - 09 May 2020
<b>ATTN : MR. JASMAN PINTO</b>		Date Reported	17 May 2020
Sample Description	<b>Hot Calorifier Tank- 1</b>		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital-AUH	Sampling Date/Time	07.05.2020/ 11:20 PM
Sample Container	1X500ml PB	Sampling Point	Tank
Sample Receipt Temp	5°C	Sample Onsite Temp	24.6°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

## TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
<b>MICROBIOLOGICAL ANALYSIS</b>				
E.coli	APHA 9222 H & I (23rd Edition)	CFU/100 ml	-	Zero
Fecal Coliforms	APHA 9222 D (23rd Edition)	CFU/100 ml	-	Zero
Pseudomonas aeruginosa	APHA 9213 E (23rd Edition)	CFU/100 ml	-	Zero
Total Bacterial Count	APHA 9215 B (23rd Edition)	CFU/ml	500	<1
Total Coliforms	APHA 9222 B (23rd Edition)	CFU/100 ml	-	Zero

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
---------	---

Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, WI: Work Instruction, NA: Not Applicable, NP: Not Provided,
----------	---


Test method deviation	None
-----------------------	------

Test performed by Emp#	74 & 55
------------------------	---------

Report prepared by Emp#	72
-------------------------	----

The above test results are only applicable to the sample(s) referred above.	
---	--

Reported By



**ANILA GEORGE**  
**LABORATORY MANAGER**



The test report shall not be reproduced (except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

**END OF REPORT**

## TEST REPORT

Report No: QMTL/R-102689/2020

<b>CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES</b> Abu Dhabi PO Box : 131463 United Arab Emirates		Sample ID	QMTL/S-102689
		Date Received	07 May 2020
		Date(s) Tested	07 May 2020 - 09 May 2020
<b>ATTN : MR. JASMAN PINTO</b>		Date Reported	17 May 2020
Sample Description	<b>Hot Calorifier Tank- 2</b>		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital-AUH	Sampling Date/Time	07.05.2020/ 11:30 PM
Sample Container	1X500ml PB	Sampling Point	Tank
Sample Receipt Temp	5°C	Sample Onsite Temp	25.2°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

## TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
<b>MICROBIOLOGICAL ANALYSIS</b>				
E.coli	APHA 9222 H & I (23rd Edition)	CFU/100 ml	-	Zero
Fecal Coliforms	APHA 9222 D (23rd Edition)	CFU/100 ml	-	Zero
Pseudomonas aeruginosa	APHA 9213 E (23rd Edition)	CFU/100 ml	-	Zero
Total Bacterial Count	APHA 9215 B (23rd Edition)	CFU/ml	500	4
Total Coliforms	APHA 9222 B (23rd Edition)	CFU/100 ml	-	Zero

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
---------	---

Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, WI: Work Instruction, NA: Not Applicable, NP: Not Provided,
----------	---


Test method deviation	None
-----------------------	------

Test performed by Emp#	74 & 55
------------------------	---------

Report prepared by Emp#	72
-------------------------	----

The above test results are only applicable to the sample(s) referred above.

Reported By



**ANILA GEORGE**  
**LABORATORY MANAGER**



The test report shall not be reproduced (except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

**END OF REPORT**

## TEST REPORT

Report No: QMTL/R-102690/2020

<b>CLIENT : CRYSTALLINE ENVIRONMENTAL SERVICES</b> Abu Dhabi PO Box : 131463 United Arab Emirates  <b>ATTN : MR. JASMAN PINTO</b>		Sample ID	QMTL/S-102690
		Date Received	07 May 2020
		Date(s) Tested	07 May 2020 - 09 May 2020
		Date Reported	17 May 2020
Sample Description	<b>Hot Calorifier Tank- 3</b>		
Sample Type	Water	Sampling Method	QMTL-WI-15
Client Name/Project	NP	Sampled By	QMTL Representative
Location	Healthpoint Hospital-AUH	Sampling Date/Time	07.05.2020/ 11:40 PM
Sample Container	1X500ml PB	Sampling Point	Tank
Sample Receipt Temp	5°C	Sample Onsite Temp	50.8°C
Sample Appearance	Clear	On-site Treatment	NA
Reference	NP		

### TEST RESULTS

PARAMETERS	TEST METHODS	UNITS	GUIDELINES	RESULTS
<b>MICROBIOLOGICAL ANALYSIS</b>				
E.coli	APHA 9222 H & I (23rd Edition)	CFU/100 ml	-	Zero
Fecal Coliforms	APHA 9222 D (23rd Edition)	CFU/100 ml	-	Zero
Pseudomonas aeruginosa	APHA 9213 E (23rd Edition)	CFU/100 ml	-	Zero
Total Bacterial Count	APHA 9215 B (23rd Edition)	CFU/ml	500	9
Total Coliforms	APHA 9222 B (23rd Edition)	CFU/100 ml	-	Zero

Remarks	The sample meets DM Water Systems quality (2010) specifications for Hot & Cold water system with respect to the above tests only.
---------	---

Keywords	CFU: Colony Forming Unit, APHA: American Public Health Association, DM: Dubai Municipality, WI: Work Instruction, NA: Not Applicable, NP: Not Provided,
----------	---

Test method deviation	None
-----------------------	------

Test performed by Emp#	74 & 55
------------------------	---------

Report prepared by Emp#	72
-------------------------	----

The above test results are only applicable to the sample(s) referred above.

Reported By



**ANILA GEORGE**  
**LABORATORY MANAGER**



The test report shall not be reproduced(except in full) without the written approval of QMTL. When analysis is witnessed by us or carried out by sub contract labs, our responsibility is solely to ensure that the analysis is conducted to standard test methods in accordance with Industry accepted practice.

**END OF REPORT**